

## GENERAL NOTES THE CONTRACTOR IS TO EMPLOY A LAND - SURVEYOR TO SET OUT THE BUILDING ON THE SITE , THE LAND - SURVEYOR IS TO CONFIRM ALL ERF BEACONS AND CORRECT SITE. THE CONTRACTOR IS TO VERIFY ALL LEVELS AND ANY DISCREPANCIES TO BE REPORTED TO THE ARCHITECT. THE CONTRACTOR IS TO LOCATE AND IDENTIFY ALL SERVICES ON SITE AND IS TO PROTECT THESE DURING THE DURATION OF THE BUILD. THE CONTRACTOR IS TO ADHERE TO ALL SPECIFICATIONS AND ALLOWED TOLERANCES AS PER SANS 10400 THAT FORM PART OF THIS DOCUMENT. ANY ERRORS , DISCREPANCIES , OR OMISSIONS ARE TO BE REPORTED TO THE ARCHITECT. CONTRACTOR IS TO BUILD IN ALL EXTERNAL DPC , WHETHER OR NOT SHOWN ON THE DRAWINGS , TO ALL EXTERNAL WALLS AT EACH FLOOR , BEAMS OR AND ALL WINDOWS, DOORS, GRILLS, OR OTHER OPENINGS IN EXTERNAL WALLS . CAVITY WALLS TO HAVE STEPPED DPC . DO NOT SCALE THIS DRAWING. ALL STRUCTURAL WALLS, BEAMS, RETAINING WALLS, POOLS LAMINATED BEAM ROOFS , OR STEEL ROOFS , STEEL , EXPOSED ROOF BEAMS PONDS WATER FEATURES, AND ANY DEMOLITION WORK TO BE SIGNED OFF BY A STRUCTURAL ENGINEER BEFORE ANY WORK DONE. CONTRACTOR TO PROVIDE ABLUTION FACILITIES FOR WORKERS IN ACCORDANCE WITH SANS10400 F THE FLOOR TO ANY LAUNDRY, KITCHEN, SHOWER ROOM, BATHROOM CONTAINING A TOILET PAN OR URINAL SHALL BE WATER - RESISTENT, AS PER SANS 10400 J. ALL WORK TO COMPLY WITH NATIONAL BUILDING REGULATIONS, LOCAL COUNCIL REGULATIONS AND THE LATEST SANS 10400 SPECIFICATIONS. ALL PLUMBING PIPES MUST BE HIDDEN IN DUCTS. ALL MEASUREMENTS TO BE CHECKED ON SITE AND ANY DISCREPANCIES TO BE REPORTED TO THE ARCHITECT. NATURAL GROUND LEVEL MUST BE BELOW 150MM BELOW THE UNFINISHED FLOOR LEVEL. ALL EXTERIOR BALCONIES AND STAIRCASES TO BE TREATED WITH APPROVED CEMENTITIOUS WATERPROOFING PENETRON AND TORCH - ON, ALL TO MANUFACTURER'S SPECIFICATIONS. NO COMBUSTABLE MATERIAL IS ALLOWED TO PASS THROUGH FIRE WALLS TRUSSES ARE NOT ALLOWED TO PASS THROUGH ANY FIRE WALLS. ALL FULLBORES TO BE PROVIDED ON BALCONIES , DETAILS AND SIZE OF OUTLET PIPES TO ENGINEER, DETAILS AND SPEC. THE ARCHITECT TAKES NO RESPONSIBILITY FOR WORK DONE BEFORE PLANS HAVE BEEN APPROVED BY LOCAL MUNC ,OR COUNCIL. ALL GLAZING IN STRICT ACCORDANCE WITH GLASS MANUFACTURERS RECOMMENDATIONS, ALL IN ACCORDANCE WITH THE NBR PART N OF SABS 0137, SABS 0400, SABS 1263 AND AAAMSA SELECTION GUIDE FOR SAFETY GLAZING MATERIALS. ALL TO AAAMSA GUIDELINES AND SPECIFICATIONS. MOTORIZED GATE ALL STRUCTURAL WORK TO ENGINEERS DETAILS AND SPECS, AND CERTIFICATION MUST BE GIVEN BY AN ENGINEER FOR ALL STRUCTURAL WORK TO BE CARRIED OUT , ALL FULBORES , STORMWATER , RETAINING , WALLS ARE TO ENGINEERS DETAILS AND SPECS. Pedestrian Gate ALL VERTICAL TANKING MUST BE DONE STRICTLY TO ENGINEERS DETAILS , A PERFORATED SLOT DRAIN , ALSO TO BE INSTALLED , BEHIND ANY RETAINING WALLS. ELECTRIC GEYSER INSTALLATION TO BE DONE IN ACCORDANCE WITH SABS 0254 AND SANS 10400. SEWERAGE BALUSTRADES TO BE MIN 1000MM, TO COMPLY WITH PART M SABS 0400 HEADROOM MIN 2100MM TO UNDERSIDE OF SLAB , FOR STAIRCASES. WATER ELECTRICAL LEGEND ALL EXTERNAL LIGHTS STAINLESS STEEL slope becomes 1:4 and steeper TEL TELEPHONE POINT Perimeter Security Fence TV - POINT 1300 WALL PLUG LIGHT SWITCH - • LIGHT SWITCH WITH DIMMER DISTRIBUTION BOARD INTERCOM $\bigcirc$ EXTERIOR WATERTIGHT LIGHT PENDANT LIGHT INTERNAL WALL MOUNTED LIGHT -• LOW VOLTAGE INTERNAL LIGHT POINT SINGLE FLOURESCENT LIGHT DOUBLE FLOURESCENT LIGHT 2 WAY TWO WAY LIGHT SWITCH STOVE ISO $\square$ VENT FOR MECHANICAL EXTRACTOR HTR POINT HEATED TOWEL RAIL ELECTRICAL POINT W/P 🔵 WATERPOINT EDDIE DA SILVA AND ASSOCIATES ARCHITECT EDDIE DA SILVA CELL 0828952760 AND ASSOCIATES CONDES@NETACTIVE.CO.ZA (SACAP reg pr.arch 7719) SAIA / CIFA REG NO 7794 WWW.EDDIEDASILVA.CO.ZA PROJECT PROPOSED NEW DWELLING FOR HOLMES FAMILY, WILDERNESS SOUTH AFRICA SITEPLAN SIGNATURE OWNER DESIGNED DRAWN EDS RNEL EDS REVISED DATE 08 AUG 2023 DATE SEPTEMBER 2024 REVISED REVISED DATE REVISED DATE REF NO DATE 08 AUG 2023

THIS DRAWING IS THE COPYRIGHT

OF EDDIE DA SILVA